


Mechanically Attached Recover

Typical Application



Color	Black
Standard Thicknesses	EPDM + Fleece: 90- and 105-mil
Standard Width	10'
Standard Length	100'

System Features and Benefits

- One of the most cost-effective recover solutions for smooth- or mineral-surfaced built-up and modified bitumen systems
- AC fleece acts as a separator between the new EPDM and the old asphalt
- EPDM is UV stable and requires no maintenance or protective coating
- 67% fewer field seams when compared to modified bitumen
- Membranes provide greater puncture resistance and 180% greater tear resistance than standard 60-mil membranes

VersiFleece AC EPDM Membrane

Versico's VersiFleece AC EPDM membrane is factory fabricated with a patented hot-melt adhesive technology. The finished sheet is comprised of VersiGard® (black) non-reinforced EPDM membrane laminated to a non-woven fleece backing (external reinforcement) and is specifically designed for recover installations. Membrane sheets are mechanically fastened to the roof deck with Versico HPV fasteners and Polymer plates. Adjoining membrane sheets are spliced together using Versico's Quick-Applied Seam Tape and Primer.



BUILDING INTEGRITY



Installation

Versico's VersiFleece AC EPDM membrane is Mechanically-Attached along the side that laps over an approved substrate to an acceptable deck using the appropriate Versico fasteners and seam plates. Seams are completed using Versico's VersiGard QA EPDM Seam Tape.

Warranty

MECHANICALLY ATTACHED RECOVER

Consult your Authorized Contractor or a Versico Independent Sales Representative for associated warranty charges.

Versico's VersiFleece AC EPDM mechanically attached system, when properly installed and inspected on a commercial project, is backed by Versico's industry leading Total System Warranty. Up to a fifteen year Total System Warranty is available when all materials used for the roofing installation are manufactured or marketed by Versico.



Existing or New Deck Type	Smooth BUR Mineral Cap Sheet or Modified Bitumen	Gravel BUR	Single-Ply
Insulation Required	None Required	Yes	None Required*
Recommended Insulation	None Required	Versico Recovery Board or Versico Recovery Board over Versico Polyiso	None Required
Insulation Attached By	N/A	Versico Fasteners/Plates	N/A
Membrane Attached By		2" Polymer Seam Plates and Fasteners	

FOR TEAR-OFF OPTIONS REFER TO NEW CONSTRUCTION ABOVE. For current code approvals and warranties, visit Versico's website or contact a design analyst.

*Except when recovering existing PVC or Ballasted Systems.



800.992.7663 • www.versico.com